



Category	Type	Quantity	Unit	Credit	Total SF	Multiplier	GS
Soils	Landscape Area w/ soil depth >= 24"	7,108	SF	Actual SF	7,108		0.6 4264.8
Groundcovers	Crushed Stone	780	SF	Actual SF	780		0.1 78.00
Plants							
Vegetation < 2' tall at maturity							
	Low Scape Mound Black Chokeberry	10	SF	Actual SF	30		0.2 6
	Pennsylvanian Sedge	2,900	SF	Actual SF	2900		0.2 580
	Bar Harbor Juniper	5	SF	Actual SF	34		0.2 6.8
	Repanda Common Juniper	18	SF	Actual SF	120		0.2 24
Vegetation at least 2' tall at maturity							
	Ninebark	1	12 SF/Plant	12	12		0.3 3.6
	Amsonia 'Blue Star'	47	12 SF/Plant	12	564		0.3 169.2
	Little Henry Sweetspire	16	12 SF/Plant	12	192		0.3 57.6
	Rainbow Leucothoe	3	12 SF/Plant	12	36		0.3 10.8
	Tufted Hair Grass	25	12 SF/Plant	12	300		0.3 90
	Little Bluestem Grass	10	12 SF/Plant	12	120		0.3 36
	Shenandoah Switch Grass	90	12 SF/Plant	12	1080		0.3 324
	Prairy Dropseed	11	12 SF/Plant	12	132		0.3 39.6
	Gray Sedge	196	13 SF/Plant	12	2352		0.3 705.6
	Winterberry Holly	8	13 SF/Plant	12	96		0.3 28.8
	Goldsturm Black Eyed Susan	19	12 SF/Plant	12	228		0.3 68.4
	Shasta Viburnum	6	12 SF/Plant	12	72		0.3 21.6
Trees							
Small (<30' Tall)							
	Canary American Holly	10	50 SF/Tree	50	500		0.6 300
Large (>30' Tall)							
	October Glory Red Maple	6	450 SF/Tree	450	2700		0.6 1620
	River birch	3	450 SF/Tree	450	1350		0.6 810
	Pin Oak	3	450 SF/Tree	450	1350		0.6 810
Engineered Landscape							
	Bioswales	1,965	SF	Actual SF	1965		1.0 1965
Bonus							
	Publicly Visible Landscape (Soil)	2,775	SF	Actual SF	2,775		0.1 277.5
	Publicly Visible Landscape (Groundcovers)	280	SF	Actual SF	280		0.1 28
	Publicly Visible Landscape (Plants < 2' tall at maturity)	1,068	SF	Actual SF	306		0.1 30.6
	Publicly Visible Landscape (Plants at least 2' tall at maturity)	133	12 SF/Plant	12	1,596		0.1 159.6
	Publicly Visible Landscape (Small trees)	10	50 SF/Tree	50	500		0.1 50
	Publicly Visible Landscape (Large trees)	7	450 SF/Tree	450	3,150		0.1 315
	Native Species (Vegetation < 2' Tall)	2,933	SF	Actual SF	3,084		0.1 308.4
	(Assumed All)						
	Native Species (Vegetation >= 2' Tall)	432	12 SF/Plant	12	5,184		0.1 518.4
	(Assumed All)						
	Native Species (Tree: Small < 30' Tall)	10	50 SF/Tree	50	500		0.1 50
	(Assumed All)						
	Native Species (Tree: Large > 30' Tall)	11	450 SF/Tree	450	4,950		0.1 495
	(Assumed All)						
	Engineered Landscape	1,965	SF	Actual SF	1,965		0.1 196.5
	De-Paved (Lot Area)	5,976	SF	Actual SF	5,976		0.1 597.6
	High Value Species (Vegetation < 2' Tall)	-	SF	Actual SF	-		0.1 0
	(Assumed All)						
	High Value Species (Vegetation >= 2' Tall)	-	12 SF/Plant	12	-		0.1 0
	(Assumed All)						
	High Value Species (Tree: Small < 30' Tall)	10	50 SF/Tree	50	500		0.1 50
	(Assumed All)						
	High Value Species (Tree: Large > 30' Tall)	6	450 SF/Tree	450	2,700		0.1 270
	(Assumed All)						
						Total	15,366
						Lot Area	72,179
						Final Green Score	0.21

PROPOSED UHAUL STORAGE FACILITY

151 LINWOOD ST - SOMERVILLE